
Scenario #1: This is as same as the project #2 requirement of Task4.

The simulation scenario should be established as below:



Link speed: 1Gbps Link length: 100 meters

The GCL should be configured for the egress of TSN_swtich1, which is connected to the TSN switch2.


The GCL content is: The units (nanoseconds, ns) should be omitted.

01111 1111, 8500ns 0000 0000, 12240ns 1000 0000, 12336ns 01111 1111, 66924ns

Hyper-period = 8500 + 12240 + 12336 + 66924 = 100 us, which is equal to the transmission interval of red flow.

Two key-indicators should be achieved:


1. Observing the window of the simulation (the figure is an example), the red stream should be sent from TSN switch1 to TSN switch2 at moment 20.74us.



2. The end-to-end delay of red flow should be a line, without any jitter.

Scenario #2:

Topology:



Flow specifications:

Source	Destination	Transmission interval	Priority
BusNode1	Host7	15ms	5
BusNode1	Host10	10ms	6
BusNode2	Host6	20ms	5
BusNode2	Host11	15ms	5
BusNode3	Host5	5ms	7
Host9	BusNode1	10ms	6
Host11	BusNode2	10ms	6
Host6	BusNode3	5ms	7

You should do:

- 1. utilize the above parameters to calculate routes and GCLs (offline routing and scheduling).
- 2. Configure the simulation by using the outputs from 1.
- 3. Edit the omnetpp.ini and .ned file, and execute the simulation.
- 4. Finally, get the simulation results.